

K2	WYKAZ STALI NR :		246_PW_K_001	01
	sprawdził MG		opracował MM	
	nr proj. nr tomu		nr rys. data	
TEMAT	REWITALIZACJA TEATRU LETNIEGO			
LOKALIZACJA				
OBSZAR / ELEMENT	FUNDAMENTY			

POZ. NR	ŚREDNICA			DŁUGOŚĆ	ILOŚĆ		ŁĄCZNA DŁUGOŚĆ																
	St 0 S	RB-500	34 GS		W 1 ELEM	RAZEM	A - 0			A - III N						A - III							
							St 0 S			RB-500						34 GS							
	mm	mm	mm	mm	szt.	szt.	4,5	6	8	6	8	12	16	20	8	10	12	16	20				
	Φ	Φ	Φ		KPL.	1	ŁAWY Ł1-Ł4																
1		12		500 000	1	1						500,0											
2		8		900	400	400					360,0												
2.1		8		740	70	70					51,8												
3		8		1 680	290	290					487,2												
3.1		8		1 600	70	70					112,0												
4		12		105 000	1	1						105,0											
5		8		260 000	1	1					260,0												
6		8		980	90	90					88,2												
7		8		1 310	180	180					235,8												
8		8		1 220	90	90					109,8												
9		12		720	82	82						59,0											
	Φ	Φ	Φ		KPL.	2	STOPA ST-1																
10		20		1 900	40	80								152,0									
11		16		1 900	20	40							76,0										
12		16		1 860	20	40							74,4										
13		16		1 840	6	12							22,1										
14		16		2 640	6	12							31,7										
15		20		2 380	8	16								38,1									
16		16		1 670	4	8							13,4										
17		16		1 900	7	14							26,6										
18		16		1 730	4	8							13,8										
	Φ	Φ	Φ		KPL.	3	STOPA ST-2																
20		20		700	20	60								42,0									
21		16		870	20	60							52,2										
22		20		1 510	4	12																	
23		8		780	4	12					9,4												
DŁUGOŚĆ RAZEM					mb						1 714	664	310	232									
MASA 1 mb					kg/m	0,125	0,222	0,395	0,222	0,395	0,888	1,578	2,466	0,395	0,617	0,888	1,578	2,466					
MASA WG ŚREDNIC					kg					676	590	489,5	572,3										
MASA WG GATUNKU					kg						2 328												
RAZEM - WYKAZ NR				EKRAN	kg	2 328																	